

Main Office
Golayee Wazirabad
PO Box 208
Kabul, Afghanistan
Phone: +93 202230752
Mobile: +93 700288232
E-mail: dacaar@dacaar.org
Website: www.dacaar.org

Supply and Installation of Drip Irrigation Tools for UNODC Project in Nangarhar Province

اعلان داوطلبی برای تهیه و نصب لوازم آبیاری سیستم قطره ای برای پروژه UNODC در ولایت ننگرهار

Date: March 12, 2026

دفتر مرکزی
گولایی وزیرآباد
پست بکس ۲۰۸
کابل، افغانستان
تلفون: +۹۳۲۰۲۲۳۰۷۵۲
موبایل: +۹۳۷۰۰۲۸۸۲۳۲
ایمیل: dacaar@dacaar.org
وبسایت: www.dacaar.org

DACAAR ITB 06 PRF-269 to 271/UNODC/2505-UNODC/UNAL1.1.7/NRM/03.2026

DACAAR invites experienced interested individuals and companies for the Supply and Installation of Drip Irrigation Tools Dara-e-Noor, Surkhrod and Kuzkunar Districts of Nangarhar Province brought up in Annex (I) and annex (II).

داکار برای تهیه و نصب لوازم آبیاری سیستم قطره ای و نصب آن در ولسوالی های دره نور، سرخ رود و کوزکنر ولایت ننگرهار ضرورت دارد و از تمام علاقمندان واجد شرایط تقاضا بعمل میآورد تا آفر های سربسته شانرا قبل از معیاد تعیین شده به دفتر داکار بسپارند.

The offers must reach DACAAR Main Office Logistics Unit located in street No. 12, Taimani Project, Qala-e-Fathullah, Kabul Province till 4:00pm April 01, 2026.

آفرها باید الی تاریخ 01 اپریل 2026 ساعت 4:00 عصر به شعبه لجستیک دفتر مرکزی داکار واقع پروژه تایمنی پایکوب نصور سرک 12 قلعه فتح الله ولایت کابل سپرده شود.

The bid opening session will be held on April 02, 2026 at 10:00am in DACAAR Main Office, Kabul Province and winner of the bidding will be notified shortly after the bid opening session.

آفرگشایی ساعت 10:00 قبل از ظهر تاریخ 02 اپریل 2026 در دفتر مرکزی داکار واقع ولایت کابل صورت میگیرد که متعاقباً برنده داوطلبی در اسرع وقت اطلاع خواهد یافت.

Terms and Conditions for the bid winner/participation

شرایط قرارداد برای برنده داوطلبی/ اشتراک کننده گان

- Supply of Drip Irrigation Tools and its Installation are in Dara-e- Noor, Surkhrood and Kuz Kunar Districts of Nangarhar Province.
- The provision of tools and installation of drip irrigation system should be completed as soon as possible, if you are unable to complete it within DACAAR tentative timeline, you can put your proposed timeline for the project completion.
- Prices should be given in Afghani (AFN) including all duties, transportation, loading and unloading costs of equipment needed for installation of drip irrigation system. Offers without sign and stamp will not be accepted. Manipulated/overwritten offers will automatically be rejected.
- The company must have enough experience in the relevant field.
- The company must have valid business license.

- تهیه لوازم آبیاری توسط سیستم قطره ای و نصب آن در ولسوالی های دره نور، سرخ رود و کوزکنر ولایت ننگرهار میباشد.
- تهیه لوازم آبیاری توسط سیستم قطره ای و نصب آن باید هر چه عاجل به پایه اكمال برسد، اگر شما در مورد زمان بندی آن مشکل داشته باشید، میتوانید مدت زمان واقعی که شما امکان تکمیل آنرا داشته باشید در آفر تان بنویسید.
- قیمت ها به افغانی داده شود و باید شامل مالیه، مصارفات انتقالات، بارگیری و تخلیه وسایل کار که در نصب سیستم قطره ای آبیاری بکار میروند باشد. آفر بدون مهر و امضا قابل قبول نمیشود. آفرهای قلم خورده گی بطور اتومات رد میگردد.
- قرارداد گیرنده باید تجربه کافی در بخش مربوطه داشته باشد.
- قرارداد گیرنده باید جواز کاری داشته باشد.

6. The bid winner must deposit 10% amount of total contract value to DACAAR bank account as a Contract Performance Guarantee before signing the genuine contract and it is refundable after successful completion of the project/work. 6. برنده داوطلبی مکلف است تا 10% مجموع ارزش قرارداد را بشکل تضمین بانکی از اجرای کامل و موفقانه قرارداد قبل از امضای آن به حساب بانکی داکار بپردازد. مبلغ متذکره در صورت اجرا موفقانه قرارداد قابل باز پرداخت میباشد.
7. Payment will be made within 25 working days after successfully completion of the work/project and confirmation of DACAAR technical team. 7. پرداخت پول بعد از تکمیل موفقانه کار/پروژه و تصدیق بخش تخنیکي در مدت 25 روز کاری میباشد.
8. In case of delay in supply and installation of drip irrigation system, 0.5% of total value of the contract will be deducted from the payment as a penalty. This penalty will be charged per each day of delay. 8. در صورت تأخیر در تهیه لوازم آبیاری توسط سیستم قطره ای و نصب آن بدون عذر موجه در وقت معینه آن، مبلغ 0.5% از ارزش مجموعی قرارداد بطور جرمانه در برابر هر روز تأخیر از طرف قرارداد گیرنده تأدیه خواهد گردید.
9. DACAAR's technical team will check all specifications of tools and installation of drip irrigation system. If it is not according to DACAAR given specifications, DACAAR reserves the right to reject the tools/work. 9. هیئت تفتیش و بررسی داکار تمام مشخصات لوازم و نصب آبیاری توسط سیستم قطره ای را مطابق قرارداد چک و ملاحظه نموده در صورتیکه مطابق مشخصات قرارداد نباشد حق دارد تا آنرا مسترد نماید.
10. Quotations should be valid for 60 working days. 10. قیمت های داده شده باید به مدت 60 روز کاری مدار اعتبار باشد.
11. 2% Tax will be applicable on the companies that have valid business license and 7% Tax will be applicable on the companies that have invalid business license, or on individuals who do not have business license, will be deducted from the contractor as a withholding tax and DACAAR will pay that amount to Ministry of Finance, the amount starts from (1 AFN). 11. 2% مالیه برای شرکت هائیکه دارای جواز با اعتبار میباشد، و 7% مالیه برای شرکت هائیکه دارای جواز بی اعتبار میباشد، و یا اشخاصیکه جواز ندارند توسط داکار وضع گردیده و به وزارت مالیه دولت افغانستان پرداخت میشود، آغاز مالیه از (1 افغانی) میباشد.
12. All bidders should deposit amount of (50,000 AFN) to DACAAR AIB Bank Afghani Account (0528101008667400) as a Bid Security, otherwise; DACAAR has the right to take the decision. 12. تمامی داوطلبان باید مبلغ 50,000 افغانی را بطور تضمین اشتراک در داوطلبی به حساب افغانی داکار (0528101008667400)، در بانک بین المللی افغانستان جمع نموده و رسید بانکی آنرا بداخل پاکت آفر بگذارند، در غیر آن داکار حق تصمیم نهایی را دارا میباشد.

Note: All deposits (Bid Security/ Contract Performance Guarantee) will be refunded on proper application of vendors along with original bank deposit slip. The deposit (bid security/ contract performance guarantee) will not be refunded, if the supplier/ bidder withdraws or quits from the process.

نوٹ: تمام تضمین ها (تضمین اشتراک در داوطلبی / تضمین اجرائیوی قرارداد) به اساس درخواست اشتراک کننده داوطلبی/ قرارداد کننده و ارایه اصل رسید بانکی پس پرداخت میگردد. داوطلب/ قرارداد گیرنده که از پروسه منصرف میگردد پول تضمین شان دوباره واپس نمیگردد.

13. DACAAR does not accept sub-contract, in case it is found that the contractor has given the contract to sub-contracting party, the contract will be automatically terminated and the contractor will lose their contract performance guarantee.
14. Award of the contract will be based on the price, quality, capacity and potentiality of bidder. The evaluation of bidder and their product will be carried out and DACAAR reserves the right to make the decision of awarding contract.
15. DACAAR (Logistics Unit) adheres to National and International laws on child labour, DACAAR makes sure all its suppliers and vendors abide by such laws preventing child labour in all DACAAR activities countrywide.
16. DACAAR has a zero-tolerance policy on sexual exploitation, abuse and harassment, which is defined and described in the policy document "DACAAR policy on preventing and handling sexual exploitation, abuse and harassment".
17. The Humanitarian Organizations (HO) may conduct on-site visit in the contractor's premises (or may take similar measures) to ensure compliance.
18. Only relevant businesses and traders can apply. Offers from the irrelevant businesses and traders will be rejected.
19. All bidders must offer prices for the whole lot with indicating prices for individual items as well. DACAAR will not accept incomplete/partial price. The bidders will be shortlisted based on the total price of each lot.
20. The bid winner must complete the project without any changes till end of the contract.
13. داکار به هیچ عنوان قرارداد دست دوم را نپذیرفته، در صورت وقوع چنین حالت قرارداد بصورت اتومات فسخ و قراردادی پول تضمین و حق اجوره خویش را از دست میدهد.
14. برنده شدن قرارداد نظر به قیمت، کیفیت، توانائی و ظرفیت داوطلب بوده و بررسی کمپنی و جنس صورت خواهد گرفت. البته داکار حق تصمیم گیری در این زمینه را دارا میباشد.
15. دفتر داکار (شعبه لوژیستیک) با در نظر داشت قوانین ملی و بین المللی برای جلوگیری از کار کودکان مصمم بوده و سعی میکند که تمام فعالیتهای تهیه کننده گان و مشتریان این اداره به این اصل پایند باشند.
16. داکار دارای پالیسی عدم تحمل در مورد سو استفاده، بد رفتاری و آزار و اذیت جنسی میباشد و موقف داکار در همچون مسایل بطور تفصیلی در پالیسی مذکور تشریح شده است.
17. سازمان های بشر دوستانه (HO) ممکن است تا از محلات و سایت ها بخاطر اطمینان بیشتر و تطبیق درست کار توسط قرارداد گیرنده بازدید بعمل آورده و یا ممکن است اقدامات مشابه را انجام دهد.
18. کمپنی های مربوطه میتواند قیمت ارایه نمایند. آفرها از مراجع نا مربوط رد میگردد.
19. تمام داوطلبان باید قیمت همه اجناس که در لات ذکر گردیده بطور جداگانه و مکمل ارایه نمایند. قیمت های جزئی و نا تکمیل قابل قبول داکار نمیشد. داوطلبان به اساس قیمت مجموعی هر لات در فهرست کوتاه شامل میگردد.
20. برنده قرارداد باید پروژه را به وجه احسن الی ختم قرارداد اكمال نماید.

For more details, please visit DACAAR Logistics Unit, Main Office Kabul-Sunday through Thursday, from 8:00am to 03:00pm. Or contact on below Email Addresses: jamal@dacaar.org or wasimullah@dacaar.org

Yours Sincerely,
 Manager – Logistics and Supply Chain
 Date: March 12, 2026,

لست ضمیمه (I) ANNEX
 فورم ارائه آفر و مشخصات تخنیکي / Budget Breakdown and Technical Specifications
 DACAAR ITB 06 PRF-269 to 271/UNODC/2505-UNODC/UNAL1.1.7/NRM/03.2026

(Lot I) Supply of Drip Irrigation Tools and Installation for Dara-e- Noor District of Nangarhar Province:

S. N	Items	Specification	Unit	Quantity	Unit Price AFN (Including 2% or 7% Tax)	Total Price AFN (Including 2% or 7% Tax)
1	Line Turbulent Dripper	line Turbulent Dripper black color (China)	No.	30000		
2	Offtake Valve for PVC pipe	Offtake Valve for PVC pipe 16mm with T type (China)	No.	250		
3	Disc Filter	2" inch Disc Filter 120BSP Male Thread (China)	No.	25		
4	LLDPE Lateral Pipe	16mm thickness 4.0 bar (China)	Meter.	60000		
5	HDPE Pipe	(50mm), SDR17 Standard quality, Suitable for drip irrigation, good quality M	Meter.	1000		
6	HDPE Pipe 1"	HDPE Pipe 1" (32mm) SDR 17, standard quality, suitable for drip irrigation M	Meter.	1500		
7	1" BSP Venturi Injector	1" BSP Venturi Injector, Flow Range (Complete Set): 1.82-6.34m ³ /h@0.7-9.5bar, suction Capacity:34-279 L/h (China)	No.	25		
8	End Line	End Line DN 16, for blocking end of the LLDPE Pipe (China)	No.	1200		
9	Straight Connector	DN 16, Made in China	No.	1200		
10	Compression Fittings Tools	(Valve End Cape, Elbow, Joint, TEE, PE Reducing Coupling, PE100 MTA (32x1") PN10)	Set.	25		
11	Manometer	Manometer 0-6bar, 60mm*1/4"(China)	No.	25		
12	Combination Air Valve	1.5"BSP (Double Action and Continuous Operation (China)	No.	25		
13	Installation	Drip system Installation cost for (75 Jeribs Orchards)	No.	75		
14	Delivery Cost	Delivery Cost	No.	1		
Transportation and Installation Cost to Dara-e Noor District of Nangarhar Province: AFN						
Grand Total: AFN						

Bidder Name: _____ اسم آفر دهنده:

Address and Stamp: _____ آدرس کمپنی و مهر کمپنی:

Contact No: _____ نمبر موبائیل:

Email Address: _____ آدرس ایمل:

Delivery Time: _____ زمان تحویلدهی:

ANEX (I) لست ضمیمه
 فورم ارائه آفر و مشخصات تخنیکي / Budget Breakdown and Technical Specifications
 DACAAR ITB 06 PRF-269 to 271/UNODC/2505-UNODC/UNAL1.1.7/NRM/03.2026

(Lot II) Supply of Drip Irrigation Tools and Installation for Surkhrood District of Nangarhar Province:

S. N	Items	Specification	Unit	Quantity	Unit Price AFN (Including 2% or 7% Tax)	Total Price AFN (Including 2% or 7% Tax)
1	Line Turbulent Dripper	line Turbulent Dripper black color (China)	No.	30,000		
2	Offtake Valve for PVC pipe	Offtake Valve for PVC pipe 16mm with T type (China)	No.	250		
3	Disc Filter	2" inch Disc Filter 120BSP Male Thread (China)	No.	25		
4	LLDPE Lateral Pipe	16mm thickness 4.0 bar (China)	Meter.	60,000		
5	HDPE Pipe	(50mm), SDR17 Standard quality, Suitable for drip irrigation, good quality M	Meter.	1,000		
6	HDPE Pipe 1"	HDPE Pipe 1" (32mm) SDR 17, standard quality, suitable for drip irrigation M	Meter.	1500		
7	1" BSP Venturi Injector	1" BSP Venturi Injector, Flow Range (Complete Set): 1.82-6.34m ³ /h@0.7-9.5bar, suction Capacity:34-279 L/h (China)	No.	25		
8	End Line	End Line DN 16, for blocking end of the LLDPE Pipe (China)	No.	1,200		
9	Straight Connector	DN 16, Made in China	No.	1,200		
10	Compression Fittings Tools	(Valve End Cape, Elbow, Joint, TEE, PE Reducing Coupling, PE100 MTA (32x1") PN10)	Set.	25		
11	Manometer	Manometer 0-6bar, 60mm*1/4"(China)	No.	25		
12	Combination Air Valve	1.5"BSP (Double Action and Continuous Operation (China)	No.	25		
13	Installation	Drip system Installation cost for (75 Jeribs Orchards)	No.	75		
14	Delivery Cost	Delivery Cost	No.	1		
Transportation and Installation Cost to Surkhrood District of Nangarhar Province: AFN						
Grand Total: AFN						

Bidder Name: _____ اسم آفر دهنده:

Address and Stamp: _____ آدرس کمپنی و مهر کمپنی:

Contact No: _____ نمبر موبائیل:

Email Address: _____ آدرس ایمل:

Delivery Time: _____ زمان تحویلدهی:

ANEX (I) لست ضمیمه
 فورم ارانه آفر و مشخصات تخنیکي /
 DACAAR ITB 06 PRF-269 to 271/UNODC/2505-UNODC/UNAL1.1.7/NRM/03.2026

(Lot III) Supply of Drip Irrigation Tools and Installation for Kuz Kunar District of Nangarhar Province:

S. N	Items	Specification	Unit	Quantity	Unit Price AFN (Including 2% or 7% Tax)	Total Price AFN (Including 2% or 7% Tax)
1	Line Turbulent Dripper	line Turbulent Dripper black color (China)	No.	30,000		
2	Offtake Valve for PVC pipe	Offtake Valve for PVC pipe 16mm with T type (China)	No.	250		
3	Disc Filter	2" inch Disc Filter 120BSP Male Thread (China)	No.	25		
4	LLDPE Lateral Pipe	16mm thickness 4.0 bar (China)	Meter.	60,000		
5	HDPE Pipe	(50mm), SDR17 Standard quality, Suitable for drip irrigation, good quality M	Meter.	1,000		
6	HDPE Pipe 1"	HDPE Pipe 1" (32mm) SDR 17, standard quality, suitable for drip irrigation M	Meter.	1,500		
7	1" BSP Venturi Injector	1" BSP Venturi Injector, Flow Range (Complete Set): 1.82-6.34m ³ /h@0.7-9.5bar, suction Capacity:34-279 L/h (China)	No.	25		
8	End Line	End Line DN 16, for blocking end of the LLDPE Pipe (China)	No.	1,200		
9	Straight Connector	DN 16, Made in China	No.	1,200		
10	Compression Fittings Tools	(Valve End Cape, Elbow, Joint, TEE, PE Reducing Coupling, PE100 MTA (32x1") PN10)	Set.	25		
11	Manometer	Manometer 0-6bar, 60mm*1/4"(China)	No.	25		
12	Combination Air Valve	1.5"BSP (Double Action and Continuous Operation (China)	No.	25		
13	Installation	Drip system Installation cost for (75 Jeribs Orchards)	No.	75		
14	Delivery Cost	Delivery Cost	No.	1		
Transportation and Installation Cost to Kuz Kunar District of Nangarhar Province: AFN						
Grand Total: AFN						

Bidder Name: _____ اسم آفر دهنده:

Address and Stamp: _____ آدرس کمپنی و مهر کمپنی:

Contact No: _____ نمبر موبائیل:

Email Address: _____ آدرس ایمل:

Delivery Time: _____ زمان تحویلدهی:

ANEX (II) لست ضمیمه
Delivery Plan / پلان کاری

DACAAR ITB 06 PRF-269 to 271/UNODC/2505-UNODC/UNAL1.1.7/NRM/03.2026

Supply of Drip Irrigation Tools and Installation for Nangarhar Province Districts:

S/N	Item Name	Specification	Unit	Quantity Based on Districts of Nangarhar Province			Total Quantity
				Dara-e-Noor	Surkhrod	Kuz Kunar	
1	Line Turbulent Dripper	line Turbulent Dripper black color (China)	No.	30,000	30,000	30,000	90,000
2	Offtake Valve for PVC pipe	Offtake Valve for PVC pipe 16mm with T type (China)	No.	250	250	250	750
3	Disc Filter	2" inch Disc Filter 120BSP Male Thread (China)	No.	25	25	25	75
4	LLDPE Lateral Pipe	16mm thickness 4.0 bar (China)	Meter.	60,000	60,000	60,000	180,000
5	HDPE Pipe	(50mm), SDR17 Standard quality, Suitable for drip irrigation, good quality M	Meter.	1,000	1,000	1,000	3,000
6	HDPE Pipe 1"	HDPE Pipe 1" (32mm) SDR 17, standard quality, suitable for drip irrigation M	Meter.	1,500	1,500	1,500	4,500
7	1" BSP Venturi Injector	1" BSP Venturi Injector, Flow Range (Complete Set): 1.82-6.34m ³ /h@0.7-9.5bar, suction Capacity:34-279 L/h (China)	No.	25	25	25	75
8	End Line	End Line DN 16, for blocking end of the LLDPE Pipe (China)	No.	1,200	1,200	1,200	3,600
9	Straight Connector	DN 16, Made in China	No.	1,200	1,200	1,200	3,600
10	Compression Fittings Tools	(Valve End Cape, Elbow, Joint, TEE, PE Reducing Coupling, PE100 MTA (32x1") PN10)	Set.	25	25	25	75
11	Manometer	Manometer 0-6bar, 60mm*1/4"(China)	No.	25	25	25	75
12	Combination Air Valve	1.5"BSP (Double Action and Continuous Operation (China)	No.	25	25	25	75
13	Installation	Drip system Installation cost for (75 Jeribs Orchards)	No.	75	75	75	225
14	Delivery Cost	Delivery Cost	No.	1	1	1	3

Start of Contract	Tentative Delivery Date	Delivery and Installation Place
Starts After DACAAR Contract Final Approval	April 30, 2026	Dara-e- Noor, Surkhrood and Kuz Kunar Districts of Nangarhar Province